

March 31, 2024

As per Ontario Regulation 652/21, Section 15, the owner, and the operator of a facility shall ensure that the required information will be updated in an Implementation Summary Table, no later than March 31st of each year.

The 2023 Implementation Summary Table is included below, which details the provisions of the Regulation that apply to the facility, along with the specific requirements for each applicable provision.

Facility	Regulation	Requirements	Implementation Status
	Section	- date when provision first applied, and	
C	(a alliana 2/2)	- date when compliance was achieved, if applicable.	5. We have do not the Coupling
Smelter/ CCNR	Section 2(2) – Applicability to	Smelter – July 1, 2023	Fully Implemented – at the Smelter
	Vale Smelter, and	CCNR – July 1, 2023	Implemented at the CCNR, with exception for
	Section 2(3) –		Section 4
	Applicability to	CCNR Section 4 – Primary off-gas capture requirement comes	
	Vale Nickel	into effect July 1 st , 2026.	
	Refinery	 Installation of Wet Gas SO₂ Scrubber scheduled for 	
		commissioning in Q1 2026 for TBRC off-gas	
Smelter	Section 3(1) –	All pyrometallurgical vessels must have primary off-gas collection	Fully Implemented
	Primary off-gas collection system	systems: – Flash furnace primary off-gas capture installed in 1994.	
	conection system	 Fluid Bed roaster off-gas capture implemented in 2006. 	
		 Pierce-Smith converters off-gas capture installed in 2008, with 	
		the completion of the Clean AER project.	
Smelter	Section 3(2)(c) -	Where applicable, pyrometallurgical vessels must have	Fully Implemented
	Secondary off-	secondary off-gas collection systems.	
	gas collection	- Converters secondary off-gas capture installed in 2018, with	
	system	the completion of Clean AER project.	
		 Section 3(4) – Secondary off-gas collection system does not 	
		apply to slag cleaner.	
		- Vale investigating implementation of Slag cleaner secondary	
		hooding; Slag Cleaner retractable secondary hooding scheduled	
CCNR	Section 3(2)(b)	for installation during PMP 2024 (April-May 2024). Where applicable, pyrometallurgical vessels must have	Fully Implemented
CCNK	and,	secondary off-gas collection systems.	r uny implemented
	Section 3(3)	 Secondary off gas concerns. Section 3(2)(b) – Secondary off-gas collection requirement does 	
		not apply to the existing CCNR top-blown rotary converters	
		(TBRCs), which were originally installed between 1970-1972. This	
Smoltor/		clause applies only to new vessels installed on or after January	
		2021.	
		 Section 3(3) – Secondary off-gas collection system does not 	
	Section 4(1)	apply to replacements in-kind of the TBRCs. Discharge of sulphur dioxide must be captured by an off-gas	Fully Implemented – at the Smelter
Smelter/ CCNR	Section 4(1)	collection system and sent to a baghouse that uses lime injection	runy implemented – at the smeller
		or to a wet scrubber.	Not implemented – at the CCNR
		– Smelter – Secondary off-gas collection system received off-gas	
		from converters and fugitive emissions from Flash Furnace	
		skimming/tapping activities. Secondary baghouse with Lime	
		injection installed with Clean AER project and completed in 2018.	
		 – CCNR – The construction of a Wet Gas SO₂ Scrubber is currently 	
		underway at the facility to capture and treat SO ₂ emissions from	
		the TBRCs.	
		 Wet Gas SO₂ Scrubber at CCNR scheduled for commissioning in O1 2026. 	
Smelter	Section 4(2)(a)	The primary off-gas from all pyrometallurgical vessels must be	Fully Implemented
Sinciter		collected, cleaned, and sent to Acid plant.	
		– Flash furnace primary off-gas capture in 1994.	
		– Fluid Bed roaster off-gas capture in 2006.	
		– Pierce-Smith converter off-gas capture in 2018 with completion	
		of Clean AER project.	
Smelter	Section 4(3)	If maintenance on acid plant or system, off-gas discharged to air.	Fully Implemented
		New stacks for discharge part of surface facility upgrade in 2019-	
		2020. Superstack and Copper Stack were decommissioned.	
		- Flash Furnace, Converters, and Fluid Bed Roasters discharge to	
		137m stacks. Acid plant discharges to 110m stack.	

VALE

Facility	Regulation	Requirements	Implementation Status
	Section	 date when provision first applied, and date when compliance was achieved, if applicable. 	
Smelter	Section 4(4)	Recommendations from a Professional engineer for operation of Acid Plant. The report was submitted to the MECP in 2023 under "Record of SO ₂ sources report". – Regulation applied to Vale effective July 1, 2023. – Implemented - Submission of report to MECP in September 2023.	Fully Implemented
Smelter/ CCNR	Section 8(1)(2)	Record of equipment at facility that discharges sulphur dioxide with date of installation and what management method is used. The report was submitted to the MECP in 2023 under "Record of SO ₂ sources report". – Regulation applied to Vale effective July 1, 2023. – Implemented - Submission of report to MECP in September 2023.	Fully Implemented
Smelter	Section 8(3)	 Professional engineer recommendations for proper operation and maintenance procedures of Vale's double contact acid plant. The report was submitted to the MECP in 2023 under "Record of SO₂ sources report". Regulation applied to Vale effective July 1, 2023. Implemented - Submission of report to MECP in September 2023. 	Fully Implemented
Smelter/ CCNR	Section 10	Applicable if changes to Managed sources, requires communication and documentation to Ministry of Environment, Conservation and Parks (MECP). No managed changes in 2023. The report was submitted to the MECP in 2023 under "Record of SO ₂ sources report". There have been no changes. – Regulation applied to Vale effective July 1, 2023. – Implemented - Submission of report to MECP in September 2023.	Fully Implemented
Smelter/ CCNR	Section 11	Applicable section if sulphur dioxide measured readings are 120 ppb or greater on an annual basis. Notification, root cause analysis, corrective and preventative actions are required. – Vale SO ₂ monitoring system (Emission reduction program) updated to track events. – No reported values 120 ppb or greater for Vale operations from July1, 2023 to December 31, 2023.	Fully Implemented
Smelter/ CCNR	Section 12	Capture Efficiency Assessment planning report required for Smelter and CCNR. – Due July 1, 2024, Capture Efficiency Assessment required for Smelter Converter aisle and NRC Converter aisle.	Not implemented
Smelter/ CCNR	Section 13	 Effectiveness report on measures to reduce concentration of sulphur dioxide at points of impingement that were implemented at the facility during the period starting January 1, 2016, to July 1, 2023. Due July 1, 2024, Effectiveness report on measures taken from January 1, 2016, to July 1, 2023. 	Not implemented
Smelter/ CCNR	Section 14	Any new implementation at facility, primary, secondary off-gas collection system fitted to a pyrometallurgical vessel or a baghouse or wet scrubber that treats discharges of sulphur dioxide from a pyrometallurgical vessel will be reported within one year to MECP. – Annual updating and review of implementation table will capture requirement.	Fully Implemented
Smelter/ CCNR	Section 15(1)	No later than March 31 of each year, implementation summary table must be updated. State when compliance was achieved. – Implemented as of March 31, 2024.	Fully Implemented
Smelter/ CCNR	Section 15(2)	Owner of facility ensures that implementation summary table is available to the public during regular business hours without charge, posting it on facility's website and making it available at the facility during regular business hours. - Implemented as of March 31, 2024.	Fully Implemented